



NOTES : SEE PLAN FOR LOCATIONS OF EXISTING FIXTURES TO REMAIN.
 PROVIDE GROUND ROD 3/4" X 8' AT EVERY OTHER POLE AND
 CONNECT TO GROUND LUGS IN POLE BASE & TO GROUND WIRE.

FOOTING NOTES:

1. FOOTING REBAR TO BE 4#9 VERTICAL WITH #3 TIES, 12" O.C.
2. BOND GRS CONDUIT, ANCHOR BOLTS, GROUND WIRE AND GROUND ROD TO LIGHT GROUND LUGS.
3. FOOTING SHALL BE CAST-IN PLACE; PRE-CAST IS NOT ACCEPTABLE.
4. ALL REINFORCED CONCRETE CONSTRUCTION AND PLACEMENT SHALL BE IN ACCORDANCE WITH ACI-318 LATEST EDITION
5. CONTRACTOR SHALL LOCATE ANCHOR BOLTS, CONDUITS, ETC. BASED ON MANUFACTURES DATA FOR EQUIPMENT SUPPLIED.

NOT TO SCALE

DRAWN BY: TS STANDARD EXT. LIGHTING 25' FIXTURE FOUNDATION

CHECKED BY: GR

PROJ #: -

DATE: 09-31-2000

DWG. # SK-11B

THE STATE UNIVERSITY OF NEW JERSEY
RUTGERS
 UNIVERSITY PLANNING AND DEVELOPMENT
 PISCATAWAY, NEW JERSEY

SK-11B